

2696-R1.docx 21 November 2014 Asset Geotechnical Engineering Pty Ltd ABN 24 093 381 107

> Email & Web info@assetgeotechnical.com.au www.assetgeotechnical.com.au

> > Sydney Suite 2.05 / 56 Delhi Road North Ryde NSW 2113 Phone: 02 9878 6005

Kosciuszko Thredbo Pty Ltd PO Box 92 Thredbo NSW 2625

By email: adam_hosie@thredbo.com.au

Dear Adam,

PROPOSED FEATHERS LODGE EXTENSION, 21 MOUNTAIN DRIVE, THREDBO GEOTECHNICAL INVESTIGATION

1. INTRODUCTION

1.1 General

This report presents the results of a geotechnical investigation for the above project. The investigation was commissioned on by Mr Adam Hosie of Kosciuszko Thredbo Pty Ltd. The work was carried out in accordance with a proposal by Asset Geotechnical Engineering Pty Ltd dated 23 September reference 2696-P1 2014.

We understand that the development will involve construction of a new deck on the western side of the lodge, which will require excavation of less than about 1m depth to form a level area for the extension and construction of new footings (Ezzy Architects drawing Hosie-Murray-S Sheet 1 Issue G, Sheet 2 Issue M, Sheet 3 Issue C).

The building is within the G line as defined in DIPNR's *"Geotechnical Policy – Kosciuszko Alpine Resorts"*, November 2003. We note that the proposed works will present a minor geotechnical impact on the site or related land, and a Form 4 "Minimal Impact Certification" in accordance with DIPNR's policy is proposed.

1.2 Scope of Work

The main objectives of the investigation were to assess the surface and subsurface conditions and to provide comments and recommendations relating to:

- Excavation conditions
- Site Classification to AS2870 'Residential Slabs and Footings' (2011)
- Suitable foundations and founding stratum
- Allowable bearing pressure
- Groundwater

In order to achieve the project objectives, the following scope of work was carried out:

- A review of existing regional maps and reports relevant to the site, held within our files.
- Visual observations of surface features.
- Excavation of two hand augered boreholes (BH1 and BH2).
- DCP testing at two main locations (BH1 and BH2), as well as an additional DCP test (DCP3) due to shallow refusal.

- Subsoil conditions were observed at a 1m deep excavation (TP1) adjacent to the site by others, for the purposes of upgrading mains water reticulation.
- Engineering assessment and reporting

This report should be read in conjunction with the attached Information Sheets. Particular attention is drawn to the limitations inherent in site investigations and the importance of verifying the subsurface conditions inferred herein. Slope instability considerations presented in this report must be read in conjunction with the attached GeoGuides for Slope Management and Maintenance.

2. FIELDWORK

Two boreholes, BH1 and BH2 were excavated to refusal on rock at 0.4m and 0.6m, respectively. DCP tests were conducted adjacent to the boreholes, an additional DCP test was conducted at a third location due to shallow refusal at BH1 and BH2 locations.

The test locations were located by tape measurements from existing site features. The subsurface conditions encountered were recorded during the excavation. Engineering logs and explanatory notes are attached to this report.

3. SITE DESCRIPTION

The site is located on the southern side of Mountain Drive in Thredbo. The site is bounded by 1 to 2 storey holiday lodges on the south and eastern sides, and by a vacant reserve to the west. Outcrops or boulders of granite extend along the western boundary of the site and into the zone of the proposed development. The overall gradient in the area locally to the site is about 5 to 10 degrees towards the east. There is an existing building on the site of timber and masonry (veneer), forming a duplex with another structure to the east.

Drainage at the site is via overland flow, following the existing gradient towards the east.

Vegetation at the site comprised grass and small to trees.

No significant protrusions, tension cracking or seepage were observed on the ground surface at the time of the site visit.

4. SUBSURFACE CONDITIONS

4.1 Geology

The Tallanagatta 1:250 000 Geological Map indicates that the site is underlain by granitic igneous rock. These rocks typically weather to form residual sandy or clay soils of medium plasticity.

4.2 Stratigraphy

The following summary description is provided for the conditions observed at the test locations for this investigation. The detailed conditions at each test location are recorded on the attached logs. For specific design input, reference should be made to the logs and/or the specific test results, in lieu of the following summary.

Layer	Description	BH1 (m)	BH2 (m)	DCP3	TP1
Topsoil / FILL	Gravelly SAND, medium grained or Silty CLAY, medium plasticity, dark brown with organic material and rootlets	0.0-0.4	0.0 – 0.5	-	0.0 – 1.0
Residual Soil	Silty CLAY, low to medium plasticity, mid brown.	0.03 – 0.7	-	-	-
Boulder? / Bedrock?	Granite, medium grained, pale yellow/pink, high strength	0.7+	0.1 – 0.13+	0.47+	-

Table 1 – Generalised Subsurface Profile

The ground conditions at the site appear to comprise FILL over shallow rock. The investigation was not able to conclusively determine if the rock encountered was bedrock, boulders placed during earthworks for the original site development, or boulders present naturally within the soil mass.

5. DISCUSSIONS & RECOMMENDATIONS

5.1 Excavation

Although excavation is expected to be minor, vibrations caused by rock excavation to nearby residential structures should be considered due to the high strength rock observed.

Excavation methods should be adopted which limit ground vibrations at the adjoining developments to not more then 10mm/sec. Vibration monitoring will be required to verify that this is achieved. However, if the contractor adopts methods and / or equipment in accordance with the recommendations in Table 2 for a ground vibration limit of 5mm/sec, vibration monitoring may not be required. The limits of 5mm/sec and 10mm/sec are expected to be achievable if rock breaker equipment or other excavation methods are restricted as indicated in Table 2 as follows:

Distance from adjoining	Maximum Peak Particle Velocity 5mm/sec		Maximum Peak Particle Velocity 10mm/sec*	
structure (m)	Equipment	Operating Limit (% of Maximum Capacity)	Equipment	Operating Limit (% of Maximum Capacity)
2.5 to 5.0	300 kg rock hammer	50	300 kg rock hammer or 600 kg rock hammer	100 50
5.0 to 10.0	300 kg rock hammer	100	600 kg rock hammer	100

Table 2 – Recommendations for Rock Breaking Equipment

* Vibration monitoring is recommended for 10mm/sec vibration limit.

At all times, the excavation equipment must be operated by experienced personnel, according to the manufacturer's instructions, and in a manner consistent with minimising vibration effects.

ASSET GEOTECHNICAL geotechnical engineering consultants

Use of other techniques (e.g. chemical rock splitting, rock sawing), although less productive, would reduce or possibly eliminate risks of damage to adjoining property through vibration effects transmitted via the ground. Such techniques may be considered if an alternative to rock breaking is necessary.

It should be noted that vibrations that are below threshold levels for building damage may be experienced at adjoining developments. However, provided that excavation controls are carried out in accordance with the recommendations for a maximum peak particle velocity of 5 mm/s, we assess that the proposed excavations would not adversely impact adjoining developments with respect to vibration.

5.2 Batter Slopes

Recommended maximum slopes for permanent and temporary batters are presented in Table 3.

Unit	Maximum Batter Slope (H : V)		
	Permanent	Temporary	
Site soils	2 : 1	1:1	
Extremely weathered granitic bedrock	1.5 : 1	0.75 : 1	
Moderately weathered bedrock	vertical *	vertical *	

Table 3 – Recommended Maximum Batter Slopes

* Subject to inspection by a geotechnical engineer and carrying out remedial works as recommended (e.g. shotcrete, rock bolting).

5.3 Lot Classification

In view of the fill at the site and the general slope instability setting, the site is assessed to be Class P (Problem site) in accordance with AS 2870–2011 "Residential Slabs and Footings". Footings should be designed in accordance with recommendations in section 5.4 of this report.

5.4 Footings

High level footings may be designed for the proposed structure for an allowable bearing capacity of 150kPa on rock or residual soil, as the rock present may represent floating boulders. Sounding of the rock after excavation for footings, or additional excavation should be conducted to ensure the load is applied centrally onto a boulder of at least 1m diameter, if a boulder is encountered and cannot be removed.

Higher bearing capacities may be attributed to continuous bedrock, however this would require additional investigation including coring of the rock and / or inspection of footing excavations.

Where some footings are to be on residual soil, and others on rock / bedrock, differential settlements are likely. In this case the structure should be designed to tolerate differential settlements by incorporating architectural joints; connecting services should also be designed accordingly.

The above classification and footing recommendations are provided on the basis that the performance expectations set out in Appendix B of AS2870–2011 are acceptable and that future site maintenance is in accordance with CSIRO BTF 18, a copy of which is attached.

An experienced geotechnical engineer should review footing designs to check that the recommendations of the geotechnical report have been included, and should assess footing excavations prior to pouring



concrete, to confirm the design assumptions. Ground conditions should be assessed during excavation of footings, to confirm the founding material is continuous bedrock and not a floating boulder.

5.5 Groundwater Control

It is anticipated that significant dewatering would not be required for the development. However, if seepage is encountered during construction, it is likely that dewatering would be controllable using conventional sump-and-pump methods.

Further advice should be sought if faster inflows are encountered during construction that cannot be controlled using this method.

6. LIMITATIONS

In addition to the limitations inherent in site investigations (refer to the attached Information Sheets), it must be pointed out that the recommendations in this report are based on assessed subsurface conditions from limited investigations. In order to confirm the assessed soil and rock properties in this report, further investigation would be required such as coring and strength testing of rock, and should be carried out if the scale of the development warrants, or if any of the properties are critical to the design, construction or performance of the development.

It is recommended that a qualified and experienced geotechnical engineer be engaged to provide further input and review during the design development; including site visits during construction to verify the site conditions and provide advice where conditions vary from those assumed in this report. Development of an appropriate inspection and testing plan should be carried out in consultation with the geotechnical engineer.

This report and details for the proposed development must be submitted to relevant regulatory authorities that have an interest in the property or are responsible for services that may be within or adjacent to the site, for their review prior to commencement of construction.

 $\circ \circ \circ \circ \circ$

Please do not hesitate to contact the undersigned if you have any questions regarding this report or if you require further assistance.

For and on behalf of **Asset Geotechnical Engineering Pty Ltd**

Mark Bartel

Mark Bartel BE MEngSc GMQ RPEQ CPEng NPER (Civil) Managing Director / Senior Principal Geotechnical Engineer

Encl:

Information Sheets (3 sheets) CSIRO BTF 18 (4 sheets) Borehole & DCP Logs (5 sheets) Figure 1 Site Locality Figure 2 Test Locations

SCOPE OF SERVICES

The geotechnical report ("the report") has been prepared in accordance with the scope of services as set out in the contract, or as otherwise agreed, between the Client and Asset Geotechnical Engineering Pty Ltd ("Asset"). The scope of work may have been limited by a range of factors such as time, budget, access and/or site disturbance constraints.

RELIANCE ON DATA

Asset has relied on data provided by the Client and other individuals and organizations, to prepare the report. Such data may include surveys, analyses, designs, maps and plans. Asset has not verified the accuracy or completeness of the data except as stated in the report. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations ("conclusions") are based in whole or part on the data, Asset will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented or otherwise not fully disclosed to Asset.

GEOTECHNICAL ENGINEERING

Geotechnical engineering is based extensively on judgment and opinion. It is far less exact than other engineering disciplines. Geotechnical engineering reports are prepared for a specific client, for a specific project and to meet specific needs, and may not be adequate for other clients or other purposes (e.g. a report prepared for a consulting civil engineer may not be adequate for a construction contractor). The report should not be used for other than its intended purpose without seeking additional geotechnical advice. Also, unless further geotechnical advice is obtained, the report cannot be used where the nature and/or details of the proposed development are changed.

LIMITATIONS OF SITE INVESTIGATION

The investigation programme undertaken is a professional estimate of the scope of investigation required to provide a general profile of subsurface conditions. The data derived from the site investigation programme and subsequent laboratory testing are extrapolated across the site to form an inferred geological model, and an engineering opinion is rendered about overall subsurface conditions and their likely behaviour with regard to the proposed development. Despite investigation, the actual conditions at the site might differ from those inferred to exist, since no subsurface exploration program, no matter how comprehensive, can reveal all subsurface details and anomalies.

The engineering logs are the subjective interpretation of subsurface conditions at a particular location and time, made by trained personnel. The actual interface between materials may be more gradual or abrupt than a report indicates.

SUBSURFACE CONDITIONS ARE TIME DEPENDENT

Subsurface conditions can be modified by changing natural forces or man-made influences. The report is based on conditions that existed at the time of subsurface exploration. Construction operations adjacent to the site, and natural events such as floods, or ground water fluctuations, may also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. Asset should be kept appraised of any such events, and should be consulted to determine if any additional tests are necessary.

VERIFICATION OF SITE CONDITIONS

Where ground conditions encountered at the site differ significantly from those anticipated in the report, it is a condition of acceptance of the report that Asset be notified of any variations and be provided with an opportunity to review the recommendations of this report. Recognition of change of soil and rock conditions requires experience and it is recommended that a suitably experienced geotechnical engineer be engaged to visit the site with sufficient frequency to detect if conditions have changed significantly.

REPRODUCTION OF REPORTS

This report is the subject of copyright and shall not be reproduced either totally or in part without the express permission of this Company. Where information from the accompanying report is to be included in contract documents or engineering specification for the project, the entire report should be included in order to minimize the likelihood of misinterpretation from logs.

REPORT FOR BENEFIT OF CLIENT

The report has been prepared for the benefit of the Client and no other party. Asset assumes no responsibility and will not be liable to any other person or organisation for or in relation to any matter dealt with or conclusions expressed in the report, or for any loss or damage suffered by any other person or organisation arising from matters dealt with or conclusions expressed in the report (including without limitation matters arising from any negligent act or omission of Asset or for any loss or damage suffered by any other party relying upon the matters dealt with or conclusions expressed in the report). Other parties should not rely upon the report or the accuracy or completeness of any conclusions and should make their own inquiries and obtain independent advice in relation to such matters.

OTHER LIMITATIONS

Asset will not be liable to update or revise the report to take into account any events or emergent circumstances or fact occurring or becoming apparent after the date of the report. **ASSET** GEOTECHNICAL geotechnical engineering consultants

NE

HE

ΒH

ΕX

DZ

R

excavation logs

natural excavation

hand excavation

backhoe bucket

excavator bucket

dozer blade

ripper tooth

Abbreviations, Notes & Symbols

METHOD

սվլ

poreno	ie logs
AS	auger screw *
AD	auger drill *
RR	roller / tricone
W	washbore
CT	cable tool
HA	hand auger
D	diatube
В	blade / blank bit
V	V-bit
Т	TC-bit

* bit shown by suffix e.g. ADV

coring

NMLC, NQ, PQ, HQ

SUPPORT

borehole logs		excavation logs		
Ν	nil	N	nil	
Μ	mud	S	shoring	
С	casing	В	benched	
NQ	NQ rods			

CORE-LIFT

		casing installed
$\frac{1}{2}$	 _	barrel withdrawn

NOTES, SAMPLES, TESTS

- disturbed D В
- bulk disturbed
- U50 thin-walled sample, 50mm diameter ΗP hand penetrometer (kPa)
- shear vane test (kPa) SV
- DCP dynamic cone penetrometer (blows per 100mm penetration) standard penetration test SPT
- N۶ SPT value (blows per 300mm)
- * denotes sample recovered SPT with solid cone Nc
- refusal of DCP or SPT R

USCS SYMBOLS

- Well graded gravels and gravel-sand mixtures, little or no fines. GW
- GΡ Poorly graded gravels and gravel-sand mixtures, little or no fines.
- Silty gravels, gravel-sand-silt mixtures. GΜ
- Clayey gravels, gravel-sand-clay mixtures. GC
- Well graded sands and gravelly sands, little or no fines. SW
- Poorly graded sands and gravelly sands, little or no fines. SP Silty sand, sand-silt mixtures.
- SM Clayey sand, sand-clay mixtures. SC
- Inorganic silts of low plasticity, very fine sands, rock flour, silty or ML clayey fine sands.
- Inorganic clays of low to medium plasticity, gravelly clays, sandy CL clays, silty clays.

DENSITY INDEX

- Organic silts and organic silty clays of low plasticity. OL
- Inorganic silts of high plasticity. MН
- Inorganic clays of high plasticity. СН
- Organic clays of medium to high plasticity. OH
- ΡT Peat muck and other highly organic soils.

MOISTURE CONDITION

- Μ moist
- W wet
- plastic limit Wp WI liquid limit

CONSISTENCY VS

S

F

St

VSt

se
dense
se

- н hard Fb friable

GRAPHIC LOG



WEATHERING

- extremely weathered XW
- highly weathered НW moderately weathered MW
 - slightly weathered
- SW FR fresh
 - М н high very high VH EH

roughness

EL

VI

L

extremely high

extremely low

very low

medium

low

RQD (%)

sum of intact core pieces > 2 x diameter x 100 total length of section being evaluated

DEFECTS

type		coating	
JT	joint	cl	clean
PT	parting	st	stained
SZ	shear zone	ve	veneer
SM	seam	CO	coating

shape р

u

ir

pl	planar	ро	polished
cu	curved	sl	slickensided
un	undulating	sm	smooth
st	stepped	ro	rough
ir	irregular	vr	very rough

inclination

measured above axis and perpendicular to core



AS1726-1993 Soils and rock are described in the following terms, which are broadly in accordance with AS1726-1993.

SOIL

MOISTURE CONDITION

Term Description

Looks and feels dry. Cohesive and cemented soils are hard, friable or powdery. Uncemented granular soils run freely through the hand. Feels cool and darkened in colour. Cohesive soils can be moulded. Dry Moist Granular soils tend to cohere.

Wet As for moist, but with free water forming on hands when handled. Moisture content of cohesive soils may also be described in relation to plastic limit (W_p) or liquid limit (W_L) [>> much greater than, > greater than, < less than, << much less than].

Density Index (%)

65 - 85

CONSISTENCY OF COHESIVE SOILS				
Term	Su (kPa)	Term	Su (kPa)	
Very soft	< 12	Very Stiff	100 – 200	
Soft	12 – 25	Hard	> 200	
Firm	25 – 50	Friable	-	
Stiff	50 - 100			

Term	Density Index(%)	Term	Den		
Very Loose	< 15	Dense	65 –		
Loose	15 – 35	Very Dense	>85		
Medium Dense	35 – 65				

PARTICLE SIZE

Name Boulders Cobbles	Subdivision	Size (mm) > 200 63 - 200
Gravel	coarse medium	20 – 63 6 – 20
	fine	2.36 - 6
Sand	coarse	0.6 - 2.36
	medium	0.2 - 0.6
	fine	0.075 – 0.2
Silt & Clay		< 0.075

MINOR COMPONENTS

Term	Proportion by Mass								
	coarse grained	fine grained							
Trace	$\leq 5\%$	≤ 15%							
Some	5 – 2%	15 – 30%							

SOIL ZONING

Layers	Continuous exposures.
Lenses	Discontinuous layers of lenticular shape.
Pockets	Irregular inclusions of different material.

SOIL CEMENTING

Weakly Easily broken up by hand. Moderately Effort is required to break up the soil by hand.

USCS SYMBOLS

Symbol	Description
GW	Well graded gravels and gravel-sand mixtures, little or no fines.
GP	Poorly graded gravels and gravel-sand mixtures, little or no fines.
GM	Silty gravels, gravel-sand-silt mixtures.
GC	Clayey gravels, gravel-sand-clay mixtures.
SW	Well graded sands and gravelly sands, little or no fines.
SP	Poorly graded sands and gravelly sands, little or no fines.
SM	Silty sand, sand-silt mixtures.
SC	Clayey sand, sand-clay mixtures.
ML	Inorganic silts of low plasticity, very fine sands, rock flour, silty or clayey fine sands.
CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays.
OL	Organic silts and organic silty clays of low plasticity.
MH	Inorganic silts of high plasticity.
СН	Inorganic clays of high plasticity.
ОН	Organic clays of medium to high plasticity.
PT	Peat muck and other highly organic soils.

ROCK

SEDIMENTARY Rock Type Conglomerate Sandstone Siltstone Claystone Shale	ROCK TYPE DEFINITIONS Definition (more than 50% of rock consists of) gravel sized (>2mm) fragments. sand sized (0.06 to 2mm) grains. silt sized (<0.06mm) particles, rock is not laminated. clay, rock is not laminated. silt or clay sized particles, rock is laminated.									
LAYERING Term Massive Poorly Developed Well Developed	Description No layering appa d Layering just visib Layering distinct. layering.	rrent. le. Little effect on p Rock breaks mor	roperties. e easily parallel to							
STRUCTURE Term Thinly laminated Laminated Very thinly bedded Thinly bedded	Spacing (mm) <6 6 - 20 20 - 60 60 - 200	Term Medium bedded Thickly bedded Very thickly bedd	Spacing 200 - 600 600 - 2,000 ed > 2,000							
STRENGTH Term Extremely Low Very Iow Low Medium	Is50 (MPa) <0.03 0.03 - 0.1 0.1 - 0.3 0.3 - 1.0 NOTE: Is50 = Point L	Term High Very High Extremely High oad Strength Inde	Is50 (MPa) 1.0 − 3.0 3.0 − 10.0 >10.0							
WEATHERING										
Term	Description									
Residual Soil	Soil derived from wea	thering of rock; th	e mass structure							
Extremely	and substance fabric are no longer evident. Rock is weathered to the extent that it has soil properties (either disintegrates or can be remoulded). Fabric of original rock is etil visible.									
Highly	Rock strength usually h	highly changed by v	weathering; rock							
Moderately	may be highly discoloured. Rock strength usually moderately changed by weathering; rock may be moderately discoloured.									
Slightly	Rock is slightly discoloured but shows little or no change of strength from fresh rock.									
TTEST	Hock shows no signs	of decomposition	or starning.							
DEFECT DESCF	RIPTION									
Joint	A surface or crack ac	ross which the roo	ck has little or no							
Parting	tensile strength. May A surface or crack ac tensile strength. Para bedding. May be ope	be open or closec ross which the roc llel or sub-parallel n or closed.	t. ok has little or no to layering/							
Sheared Zone	Zone of rock substant nar, curved or undula	ce with roughly pa ting boundaries ci	arallel, near pla- ut by closely ar defects							
Seam	Seam with deposited insitu rock (XW), or di of the host rock (crus	soil (infill), extrem isoriented usually hed).	ely weathered angular fragments							
Shape Bloper	Consistent orit-t									
Curved	Gradual change in ori	1. ientation								
Undulating	Wavy surface.	iontation.								
Stepped	One or more well defined	ned steps. in orientation								
- .	many onarp onangoo									
Roughness Polished	Shiny smooth surface	3								
Slickensided	Grooved or striated s	 urface, usually pol	lished.							
Smooth	Smooth to touch. Few	v or no surface irre	egularities.							
Very Rough	<1mm). Feels like fin Many large surface in	e to coarse sandp regularities, amplit	aper. tude generally							
	>1mm. Feels like ver	y coarse sandpap	er.							
Coating										
Clean	No visible coating or	discolouring.								
Stained Veneer	No visible coating but A visible coating of so	t surfaces are disc	coloured. thin to measure:							
Coating	may be patchy Visible coating ≤1mm scribed as seam.	n thick. Thicker so	il material de-							

Foundation Maintenance and Footing Performance: A Homeowner's Guide



BTF 18 replaces Information Sheet 10/91

Buildings can and often do move. This movement can be up, down, lateral or rotational. The fundamental cause of movement in buildings can usually be related to one or more problems in the foundation soil. It is important for the homeowner to identify the soil type in order to ascertain the measures that should be put in place in order to ensure that problems in the foundation soil can be prevented, thus protecting against building movement.

This Building Technology File is designed to identify causes of soil-related building movement, and to suggest methods of prevention of resultant cracking in buildings.

Soil Types

The types of soils usually present under the topsoil in land zoned for residential buildings can be split into two approximate groups – granular and clay. Quite often, foundation soil is a mixture of both types. The general problems associated with soils having granular content are usually caused by erosion. Clay soils are subject to saturation and swell/shrink problems.

Classifications for a given area can generally be obtained by application to the local authority, but these are sometimes unreliable and if there is doubt, a geotechnical report should be commissioned. As most buildings suffering movement problems are founded on clay soils, there is an emphasis on classification of soils according to the amount of swell and shrinkage they experience with variations of water content. The table below is Table 2.1 from AS 2870, the Residential Slab and Footing Code.

Causes of Movement

Settlement due to construction

There are two types of settlement that occur as a result of construction:

- Immediate settlement occurs when a building is first placed on its foundation soil, as a result of compaction of the soil under the weight of the structure. The cohesive quality of clay soil mitigates against this, but granular (particularly sandy) soil is susceptible.
- Consolidation settlement is a feature of clay soil and may take place because of the expulsion of moisture from the soil or because of the soil's lack of resistance to local compressive or shear stresses. This will usually take place during the first few months after construction, but has been known to take many years in exceptional cases.

These problems are the province of the builder and should be taken into consideration as part of the preparation of the site for construction. Building Technology File 19 (BTF 19) deals with these problems.

Erosion

All soils are prone to erosion, but sandy soil is particularly susceptible to being washed away. Even clay with a sand component of say 10% or more can suffer from erosion.

Saturation

This is particularly a problem in clay soils. Saturation creates a boglike suspension of the soil that causes it to lose virtually all of its bearing capacity. To a lesser degree, sand is affected by saturation because saturated sand may undergo a reduction in volume – particularly imported sand fill for bedding and blinding layers. However, this usually occurs as immediate settlement and should normally be the province of the builder.

Seasonal swelling and shrinkage of soil

All clays react to the presence of water by slowly absorbing it, making the soil increase in volume (see table below). The degree of increase varies considerably between different clays, as does the degree of decrease during the subsequent drying out caused by fair weather periods. Because of the low absorption and expulsion rate, this phenomenon will not usually be noticeable unless there are prolonged rainy or dry periods, usually of weeks or months, depending on the land and soil characteristics.

The swelling of soil creates an upward force on the footings of the building, and shrinkage creates subsidence that takes away the support needed by the footing to retain equilibrium.

Shear failure

This phenomenon occurs when the foundation soil does not have sufficient strength to support the weight of the footing. There are two major post-construction causes:

- Significant load increase.
- Reduction of lateral support of the soil under the footing due to erosion or excavation.
- In clay soil, shear failure can be caused by saturation of the soil adjacent to or under the footing.

GENERAL DEFINITIONS OF SITE CLASSES								
Class	Foundation							
А	Most sand and rock sites with little or no ground movement from moisture changes							
S	Slightly reactive clay sites with only slight ground movement from moisture changes							
М	Moderately reactive clay or silt sites, which can experience moderate ground movement from moisture changes							
Н	Highly reactive clay sites, which can experience high ground movement from moisture changes							
Е	Extremely reactive sites, which can experience extreme ground movement from moisture changes							
A to P	Filled sites							
Р	Sites which include soft soils, such as soft clay or silt or loose sands; landslip; mine subsidence; collapsing soils; soils subject to erosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise							

Tree root growth

Trees and shrubs that are allowed to grow in the vicinity of footings can cause foundation soil movement in two ways:

- Roots that grow under footings may increase in cross-sectional size, exerting upward pressure on footings.
- Roots in the vicinity of footings will absorb much of the moisture in the foundation soil, causing shrinkage or subsidence.

Unevenness of Movement

The types of ground movement described above usually occur unevenly throughout the building's foundation soil. Settlement due to construction tends to be uneven because of:

- Differing compaction of foundation soil prior to construction.
- Differing moisture content of foundation soil prior to construction.

Movement due to non-construction causes is usually more uneven still. Erosion can undermine a footing that traverses the flow or can create the conditions for shear failure by eroding soil adjacent to a footing that runs in the same direction as the flow.

Saturation of clay foundation soil may occur where subfloor walls create a dam that makes water pond. It can also occur wherever there is a source of water near footings in clay soil. This leads to a severe reduction in the strength of the soil which may create local shear failure

Seasonal swelling and shrinkage of clay soil affects the perimeter of the building first, then gradually spreads to the interior. The swelling process will usually begin at the uphill extreme of the building, or on the weather side where the land is flat. Swelling gradually reaches the interior soil as absorption continues. Shrinkage usually begins where the sun's heat is greatest.

Effects of Uneven Soil Movement on Structures

Erosion and saturation

Erosion removes the support from under footings, tending to create subsidence of the part of the structure under which it occurs. Brickwork walls will resist the stress created by this removal of support by bridging the gap or cantilevering until the bricks or the mortar bedding fail. Older masonry has little resistance. Evidence of failure varies according to circumstances and symptoms may include:

- Step cracking in the mortar beds in the body of the wall or above/below openings such as doors or windows.
- Vertical cracking in the bricks (usually but not necessarily in line with the vertical beds or perpends).

Isolated piers affected by erosion or saturation of foundations will eventually lose contact with the bearers they support and may tilt or fall over. The floors that have lost this support will become bouncy, sometimes rattling ornaments etc.

Seasonal swelling/shrinkage in clay

Swelling foundation soil due to rainy periods first lifts the most exposed extremities of the footing system, then the remainder of the perimeter footings while gradually permeating inside the building footprint to lift internal footings. This swelling first tends to create a dish effect, because the external footings are pushed higher than the internal ones.

The first noticeable symptom may be that the floor appears slightly dished. This is often accompanied by some doors binding on the floor or the door head, together with some cracking of cornice mitres. In buildings with timber flooring supported by bearers and joists, the floor can be bouncy. Externally there may be visible dishing of the hip or ridge lines.

As the moisture absorption process completes its journey to the innermost areas of the building, the internal footings will rise. If the spread of moisture is roughly even, it may be that the symptoms will temporarily disappear, but it is more likely that swelling will be uneven, creating a difference rather than a disappearance in symptoms. In buildings with timber flooring supported by bearers and joists, the isolated piers will rise more easily than the strip footings or piers under walls, creating noticeable doming of flooring.

Trees can cause shrinkage and damage



As the weather pattern changes and the soil begins to dry out, the external footings will be first affected, beginning with the locations where the sun's effect is strongest. This has the effect of lowering the external footings. The doming is accentuated and cracking reduces or disappears where it occurred because of dishing, but other cracks open up. The roof lines may become convex.

Doming and dishing are also affected by weather in other ways. In areas where warm, wet summers and cooler dry winters prevail, water migration tends to be toward the interior and doming will be accentuated, whereas where summers are dry and winters are cold and wet, migration tends to be toward the exterior and the underlying propensity is toward dishing.

Movement caused by tree roots

In general, growing roots will exert an upward pressure on footings, whereas soil subject to drying because of tree or shrub roots will tend to remove support from under footings by inducing shrinkage.

Complications caused by the structure itself

Most forces that the soil causes to be exerted on structures are vertical - i.e. either up or down. However, because these forces are seldom spread evenly around the footings, and because the building resists uneven movement because of its rigidity, forces are exerted from one part of the building to another. The net result of all these forces is usually rotational. This resultant force often complicates the diagnosis because the visible symptoms do not simply reflect the original cause. A common symptom is binding of doors on the vertical member of the frame.

Effects on full masonry structures

Brickwork will resist cracking where it can. It will attempt to span areas that lose support because of subsided foundations or raised points. It is therefore usual to see cracking at weak points, such as openings for windows or doors.

In the event of construction settlement, cracking will usually remain unchanged after the process of settlement has ceased.

With local shear or erosion, cracking will usually continue to develop until the original cause has been remedied, or until the subsidence has completely neutralised the affected portion of footing and the structure has stabilised on other footings that remain effective.

In the case of swell/shrink effects, the brickwork will in some cases return to its original position after completion of a cycle, however it is more likely that the rotational effect will not be exactly reversed, and it is also usual that brickwork will settle in its new position and will resist the forces trying to return it to its original position. This means that in a case where swelling takes place after construction and cracking occurs, the cracking is likely to at least partly remain after the shrink segment of the cycle is complete. Thus, each time the cycle is repeated, the likelihood is that the cracking will become wider until the sections of brickwork become virtually independent.

With repeated cycles, once the cracking is established, if there is no other complication, it is normal for the incidence of cracking to stabilise, as the building has the articulation it needs to cope with the problem. This is by no means always the case, however, and monitoring of cracks in walls and floors should always be treated seriously.

Upheaval caused by growth of tree roots under footings is not a simple vertical shear stress. There is a tendency for the root to also exert lateral forces that attempt to separate sections of brickwork after initial cracking has occurred.

The normal structural arrangement is that the inner leaf of brickwork in the external walls and at least some of the internal walls (depending on the roof type) comprise the load-bearing structure on which any upper floors, ceilings and the roof are supported. In these cases, it is internally visible cracking that should be the main focus of attention, however there are a few examples of dwellings whose external leaf of masonry plays some supporting role, so this should be checked if there is any doubt. In any case, externally visible cracking is important as a guide to stresses on the structure generally, and it should also be remembered that the external walls must be capable of supporting themselves.

Effects on framed structures

Timber or steel framed buildings are less likely to exhibit cracking due to swell/shrink than masonry buildings because of their flexibility. Also, the doming/dishing effects tend to be lower because of the lighter weight of walls. The main risks to framed buildings are encountered because of the isolated pier footings used under walls. Where erosion or saturation cause a footing to fall away, this can double the span which a wall must bridge. This additional stress can create cracking in wall linings, particularly where there is a weak point in the structure caused by a door or window opening. It is, however, unlikely that framed structures will be so stressed as to suffer serious damage without first exhibiting some or all of the above symptoms for a considerable period. The same warning period should apply in the case of upheaval. It should be noted, however, that where framed buildings are supported by strip footings there is only one leaf of brickwork and therefore the externally visible walls are the supporting structure for the building. In this case, the subfloor masonry walls can be expected to behave as full brickwork walls.

Effects on brick veneer structures

Because the load-bearing structure of a brick veneer building is the frame that makes up the interior leaf of the external walls plus perhaps the internal walls, depending on the type of roof, the building can be expected to behave as a framed structure, except that the external masonry will behave in a similar way to the external leaf of a full masonry structure.

Water Service and Drainage

Where a water service pipe, a sewer or stormwater drainage pipe is in the vicinity of a building, a water leak can cause erosion, swelling or saturation of susceptible soil. Even a minuscule leak can be enough to saturate a clay foundation. A leaking tap near a building can have the same effect. In addition, trenches containing pipes can become watercourses even though backfilled, particularly where broken rubble is used as fill. Water that runs along these trenches can be responsible for serious erosion, interstrata seepage into subfloor areas and saturation.

Pipe leakage and trench water flows also encourage tree and shrub roots to the source of water, complicating and exacerbating the problem.

Poor roof plumbing can result in large volumes of rainwater being concentrated in a small area of soil:

Incorrect falls in roof guttering may result in overflows, as may gutters blocked with leaves etc.

- Corroded guttering or downpipes can spill water to ground.
- Downpipes not positively connected to a proper stormwater collection system will direct a concentration of water to soil that is directly adjacent to footings, sometimes causing large-scale problems such as erosion, saturation and migration of water under the building.

Seriousness of Cracking

In general, most cracking found in masonry walls is a cosmetic nuisance only and can be kept in repair or even ignored. The table below is a reproduction of Table C1 of AS 2870.

AS 2870 also publishes figures relating to cracking in concrete floors, however because wall cracking will usually reach the critical point significantly earlier than cracking in slabs, this table is not reproduced here.

Prevention/Cure

Plumbing

Where building movement is caused by water service, roof plumbing, sewer or stormwater failure, the remedy is to repair the problem. It is prudent, however, to consider also rerouting pipes away from the building where possible, and relocating taps to positions where any leakage will not direct water to the building vicinity. Even where gully traps are present, there is sometimes sufficient spill to create erosion or saturation, particularly in modern installations using smaller diameter PVC fixtures. Indeed, some gully traps are not situated directly under the taps that are installed to charge them, with the result that water from the tap may enter the backfilled trench that houses the sewer piping. If the trench has been poorly backfilled, the water will either pond or flow along the bottom of the trench. As these trenches usually run alongside the footings and can be at a similar depth, it is not hard to see how any water that is thus directed into a trench can easily affect the foundation's ability to support footings or even gain entry to the subfloor area.

Ground drainage

In all soils there is the capacity for water to travel on the surface and below it. Surface water flows can be established by inspection during and after heavy or prolonged rain. If necessary, a grated drain system connected to the stormwater collection system is usually an easy solution.

It is, however, sometimes necessary when attempting to prevent water migration that testing be carried out to establish watertable height and subsoil water flows. This subject is referred to in BTF 19 and may properly be regarded as an area for an expert consultant.

Protection of the building perimeter

It is essential to remember that the soil that affects footings extends well beyond the actual building line. Watering of garden plants, shrubs and trees causes some of the most serious water problems.

For this reason, particularly where problems exist or are likely to occur, it is recommended that an apron of paving be installed around as much of the building perimeter as necessary. This paving

CLASSIFICATION OF DAMAGE WITH REFERENCE TO WALLS								
Description of typical damage and required repair	Approximate crack width limit (see Note 3)	Damage category						
Hairline cracks	<0.1 mm	0						
Fine cracks which do not need repair	<1 mm	1						
Cracks noticeable but easily filled. Doors and windows stick slightly	<5 mm	2						
Cracks can be repaired and possibly a small amount of wall will need to be replaced. Doors and windows stick. Service pipes can fracture. Weathertightness often impaired	5–15 mm (or a number of cracks 3 mm or more in one group)	3						
Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows. Window and door frames distort. Walls lean or bulge noticeably, some loss of bearing in beams. Service pipes disrupted	15–25 mm but also depend on number of cracks	4						



should extend outwards a minimum of 900 mm (more in highly reactive soil) and should have a minimum fall away from the building of 1:60. The finished paving should be no less than 100 mm below brick vent bases.

It is prudent to relocate drainage pipes away from this paving, if possible, to avoid complications from future leakage. If this is not practical, earthenware pipes should be replaced by PVC and backfilling should be of the same soil type as the surrounding soil and compacted to the same density.

Except in areas where freezing of water is an issue, it is wise to remove taps in the building area and relocate them well away from the building – preferably not uphill from it (see BTF 19).

It may be desirable to install a grated drain at the outside edge of the paving on the uphill side of the building. If subsoil drainage is needed this can be installed under the surface drain.

Condensation

In buildings with a subfloor void such as where bearers and joists support flooring, insufficient ventilation creates ideal conditions for condensation, particularly where there is little clearance between the floor and the ground. Condensation adds to the moisture already present in the subfloor and significantly slows the process of drying out. Installation of an adequate subfloor ventilation system, either natural or mechanical, is desirable.

Warning: Although this Building Technology File deals with cracking in buildings, it should be said that subfloor moisture can result in the development of other problems, notably:

- Water that is transmitted into masonry, metal or timber building elements causes damage and/or decay to those elements.
- High subfloor humidity and moisture content create an ideal environment for various pests, including termites and spiders.
- Where high moisture levels are transmitted to the flooring and walls, an increase in the dust mite count can ensue within the living areas. Dust mites, as well as dampness in general, can be a health hazard to inhabitants, particularly those who are abnormally susceptible to respiratory ailments.

The garden

The ideal vegetation layout is to have lawn or plants that require only light watering immediately adjacent to the drainage or paving edge, then more demanding plants, shrubs and trees spread out in that order.

Overwatering due to misuse of automatic watering systems is a common cause of saturation and water migration under footings. If it is necessary to use these systems, it is important to remove garden beds to a completely safe distance from buildings.

Existing trees

Where a tree is causing a problem of soil drying or there is the existence or threat of upheaval of footings, if the offending roots are subsidiary and their removal will not significantly damage the tree, they should be severed and a concrete or metal barrier placed vertically in the soil to prevent future root growth in the direction of the building. If it is not possible to remove the relevant roots without damage to the tree, an application to remove the tree should be made to the local authority. A prudent plan is to transplant likely offenders before they become a problem.

Information on trees, plants and shrubs

State departments overseeing agriculture can give information regarding root patterns, volume of water needed and safe distance from buildings of most species. Botanic gardens are also sources of information. For information on plant roots and drains, see Building Technology File 17.

Excavation

Excavation around footings must be properly engineered. Soil supporting footings can only be safely excavated at an angle that allows the soil under the footing to remain stable. This angle is called the angle of repose (or friction) and varies significantly between soil types and conditions. Removal of soil within the angle of repose will cause subsidence.

Remediation

Where erosion has occurred that has washed away soil adjacent to footings, soil of the same classification should be introduced and compacted to the same density. Where footings have been undermined, augmentation or other specialist work may be required. Remediation of footings and foundations is generally the realm of a specialist consultant.

Where isolated footings rise and fall because of swell/shrink effect, the homeowner may be tempted to alleviate floor bounce by filling the gap that has appeared between the bearer and the pier with blocking. The danger here is that when the next swell segment of the cycle occurs, the extra blocking will push the floor up into an accentuated dome and may also cause local shear failure in the soil. If it is necessary to use blocking, it should be by a pair of fine wedges and monitoring should be carried out fortnightly.

This BTF was prepared by John Lewer FAIB, MIAMA, Partner, Construction Diagnosis.

The information in this and other issues in the series was derived from various sources and was believed to be correct when published.

The information is advisory. It is provided in good faith and not claimed to be an exhaustive treatment of the relevant subject.

Further professional advice needs to be obtained before taking any action based on the information provided.

Distributed by

CSIRO PUBLISHING PO Box 1139, Collingwood 3066, Australia Freecall 1800 645 051 Tel (03) 9662 7666 Fax (03) 9662 7555 www.publish.csiro.au Email: publishing.sales@csiro.au

© CSIRO 2003. Unauthorised copying of this Building Technology file is prohibited



SYDNEY Suite 2.05 / 56 Delhi Rd North Ryde NSW 2113

Asset Geotechnical Engineering Pty Ltd info@assetgeotechnical.com.au

BH1

1 of 1

BH no:

sheet:

orehole Log					j	ob no.:	2696
client: principal:	KOSCIUSZKO) THREDBO P	TY LTD		s f	started: inished	21.10.2014 : 21.10.2014
project:	PROPOSED F	EATHERS LO	DGE EXTENSION		I	ogged:	JAH
location:	21 MOUNTA	IN DRIVE, TH	REDBO			checked	: MAB
diameter:	100mm	inclination: -	00° bearing: E: N:		с С	datum:	ce. approx
drilling informati	ion	material in	ormation				-
pd .	etc s	ic log symbol	material description	stency/ ty index	hand penetro- meter	structure and additional observations	
suppo water notes	sampi tests, RL depth metre	graph USCS	soil type: plasticity or particle characteristics, colour, secondary and minor components.	moist condi	consis densit	kPa 800 00 00 10 00 00 10 00 00 10 000 10 00 10 00 10 10 00 10 10 00 10 10 10 10 10 10 10 10 10 10 10 10 1	
HA H			Colour, secondary and minor components. Gravelly SAND, fine to medium grained, dark brown, with of cobbles of granite, 40mm dia. Sandy GRAVEL, fine to medium grained, brown. Gravel is angular, fine grained. Borehole No: BH1 terminated at 0.4m		-		FILL / TOPSOIL FILL / TOPSOIL FILL / APPARENTLY COMPACTED HA refusal on GRANITE, medium grained moderately to slightly weathered.
	1.0						Developing Provide 10



Asset Geotechnical Engineering Pty Ltd info@assetgeotechnical.com.au SYDNEY Suite 2.05 / 56 Delhi Rd North Ryde NSW 2113

BH2

1 of 1

BH no:

sheet:

Bo	reł	nol	le	Log
			_	0

Borehole Log								Ph: 02 9878 6005 Fax: 02 8282 5011	j	ob no.:	2696		
client:KOSCIUSZKOprincipal:PROPOSED Fproject:PROPOSED F						THRE	DBO PT	TY LTD DGE EXTENSION	ء 1 ا	started: inished ogged:	21.10.2014 : 21.10.2014 JAH		
loca	tion	:	2	21 MC	DUNTA	IN DRI	VE, TH	REDBO		(checked	: MAB	
equ	ipme	ent:	F 1	IA 00m	m	inclines	·			I	RL surfa	ce: approx.	
dril	ling i	nfor	mation	.00111	111	mate	erial inf	ormation			Jatum:		
											4		
iethod	upport	ater (otes amples, ests, etc	_	epth ietres	raphic log	SCS symbol	material description soil type: plasticity or particle characteristics,	oisture	onsistency/ ensity index	structure and benefic additional observation		
4	N N	5	t o p	~	20	<u>88 68 88</u> 00		colour, secondary and minor components.	>Wn	- 0	100 00 00 00 00 00 00 00 00 00 00 00 00	TOPSOIL / FILL	
7H								with some organic material and rootlets.				-	
					0.5			Silty CLAY, low to medium plasticity, mid brown.		F		RESIDUAL? / FILL?	
					- 0.6 			Borehole No: BH2 terminated at 0.6m				HA refusal on GRANITE, medium grained moderately to slightly weathered. –	
REF	ER TO) FXP		SHFF	TS FOR D	DESCRIPT	ION OF	ERMS AND SYMBOLS USED				Borehole Log - Revision 10	

2696 LOGS.GPJ 27/10/14



	GEOTE	CHN	VICA	L		i	Asset G info@a	Geotec ssetge	hnical Engineer	ing Pty Ltd .au		Test No:	BH1	
ninkanni geolechnical engineening consultants						:	SYDNE 2.05 / 5	Y 6 Delh	ii Road	Sheet:	1 of 1			
Dynamic (Cone P	ene	etror	net	er		North R Ph: 02 Fax: 02	Ryde N 9878 2 8282	SW 2113 6005 5011			Job no:	2696	
client:	KOSCIUS	ZKO	THRE	ОВО	PTY LT	D						started:	21/10/2	2014
principal:												finished:	21/10/2	2014
project:	PROPOSI	ED FE	EATHE	RS L	ODGE	EXT	ENSI	ON				logged:	JAH	
location:	21 MOUN	TAIN	DRIVE	E, THI	REDBO)						checked:	MAB	
equipment:	9kg hammer, 510mm drop, cone tipRL:													
standard:	AS1289.6.3.2-1997 datum:													
Donth (m)	Blows /		Plot (b	lows/	100mm	vs de	epth)		Soil Type	Inferre	d Paramet	ers (not to t	be used for	design)
Depth (III)	100mm	0	5	10	15		20	25	g-granular	Index	Phi (°)	sistency	Cu (kPa)	E (MPa)
0.00 - 0.10	1								g	L	30			7
0.10 - 0.20	5								g	VD	36			33
0.20 - 0.30	4		4						g	VD	35			26
0.30 - 0.40 0.40 - 0.50			Calia			`								
0.50 - 0.60			50110	reiusa	ai at 0.50	0111	_							
0.60 - 0.70														
0.70 - 0.80														
0.80 - 0.90 0.90 - 1.00														
1.00 - 1.10														
1.10 – 1.20														
1.20 - 1.30														
1.30 - 1.40 1.40 - 1.50														
1.50 - 1.60														
1.60 – 1.70														
1.70 - 1.80														
1.80 - 1.90 1.90 - 2.00														
2.00 - 2.10														
2.10 – 2.20														
2.20 - 2.30														
2.30 - 2.40 2.40 - 2.50														
2.50 - 2.60														
2.60 - 2.70														
2.70 - 2.80														
2.80 - 2.90 2.90 - 3.00														
3.00 - 3.10														
3.10 - 3.20														
3.20 - 3.30														
3.40 - 3.50														
3.50 - 3.60														
3.60 - 3.70														
3.70 - 3.80 3.80 - 3.90														
3.90 - 4.00														
4.00 - 4.10														
4.10 - 4.20														
4.20 - 4.30 4.30 - 4.40														
4.40 - 4.50														
4.50 - 4.60														
4.60 - 4.70														
4.70 - 4.80 4.80 - 4.90														
4.90 - 5.00														
Notes:	· · · ·													
Practical refusal = 2	25+ blows pe	er 100r	nm, "So aramet	olid" re are	etusal =	no fur	ther pe	enetra	ation and "soli	d" ringing s	ound from s	lide hamme	er	
mounicient uata l		mea h	aramett	513										

Refer to Information Sheets for Terms and Symbols



	GEOTE	CH	VICAI	_		Asse info@	t Geotec Dassetge	hnical Engineer	ing Pty Ltd .au		Test No:	BH2	
IIIh. IIIII geotechnica	ai engineeri	ing coi	nsultant	S		SYD 2.05	NEY / 56 Delł	ni Road			Sheet:	1 of 1	
Dynamic (Cone P	ene	etron	nete	er	North Ph: Fax:	n Ryde N 02 9878 02 8282	SW 2113 6005 5011			Job no:	2696	
client:	KOSCIUSZKO THREDBO PTY LTD								started: 21/10/2014				
principal:											finished:	21/10/2	2014
project:	PROPOSED FEATHERS LODGE EXTENSION								logged:	JAH			
location:	21 MOUNTAIN DRIVE, THREDBO							checked:	MAB				
equipment:	9kg hammer, 510mm drop, cone tip								RL:				
standard:	AS1289.6	5.3.2-1	997				-				datum:		
Depth (m)	Blows / 100mm	Blows / Plot (blows/100mm vs 100mm 0 5 10 15) 25	c-cohesive	Density	Phi (°)	ers (not to l	Cu (kPa)	design) E (MPa)
0.00 - 0.10	2	1.						C	Index		F	40	24
0.10 - 0.20	2	I						с			F	40	24
0.20 - 0.30	2							с			F	40	24
0.30 - 0.40	2	- ↓ ↓						C			F	40	24
0.40 - 0.50	2	. ↓						C				40	24
0.50 - 0.60	2	•						C			F	40	24
0.70 - 0.80													
0.80 - 0.90			Solid	d refus	al at 0.65	im							
0.90 - 1.00													
1.00 - 1.10													
1.10 - 1.20 1.20 - 1.30													
1.30 - 1.40													
1.40 - 1.50													
1.50 - 1.60													
1.60 - 1.70													
1.70 - 1.80													
1.80 - 1.90 1.90 - 2.00													
2.00 - 2.10													
2.10 - 2.20													
2.20 - 2.30													
2.30 - 2.40													
2.50 - 2.60													
2.60 - 2.70													
2.70 - 2.80													
2.80 - 2.90													
2.90 - 3.00 3.00 - 3.10													
3.10 - 3.20													
3.20 - 3.30													
3.30 - 3.40													
3.40 - 3.50													
3.50 - 3.60 3.60 - 3.70													
3.70 - 3.80													
3.80 - 3.90													
3.90 - 4.00													
4.00 - 4.10													
4.10 - 4.20													
4.20 - 4.30 4.30 - 4.40													
4.40 - 4.50													
4.50 - 4.60													
4.60 - 4.70													
4.70 - 4.80													
4.80 - 4.90													
4.90 - 5.00													
Practical refusal = 25+ blows per 100mm, "Solid" refusal = no further penetration and "solid" ringing sound from slide hammer													
** Insufficient data	to derive infe	erred p	aramete	ers									
Refer to Information S	Sheets for Terr	ms and	Symbols									DCP Log -	Revision 17



	GEOTE	CHNI	CAL			Asset (info@a	Geotecl ssetge	nnical Engineer otechnical.com	ing Pty Ltd .au		Test No:	DCP3	
IIIhIIII geotechnica	al engineerir	ng consu	Itants			SYDNE 2.05 / 5	EY 56 Delh	i Road			Sheet:	1 of 1	
Dynamic (Cone P	enetr	ome	ter		North F Ph: 02 Fax: 02	Ryde N 9878 6 2 8282	SW 2113 5005 5011			Job no:	2696	
client:	KOSCIUS	ZKO TH	REDBO) PTY	LTD						started:	21/10/2	2014
principal:											finished:	21/10/2	2014
project:	PROPOSE		THERS	LODG	E EXT	FENSI	ON				logged:	JAH	
location:	21 MOUNTAIN DRIVE, THREDBO								checked:	MAB			
equipment:	9kg hammer, 510mm drop, cone tip								RL:				
standard:	AS1289.6.	.3.2-199	7								datum:		
	Blows /	Plo	ers (not to b	be used for	design)								
Depth (m)	100mm	0 5	5 1	0 1	5	20	25	c-cohesive g-granular	Density Index	Phi (°)	Con- sistency	Cu (kPa)	E (MPa)
0.00 - 0.10	1							С			S	20	12
0.10 - 0.20	4							C			St	80	48
0.20 - 0.30	4							C			SI VSt	00 140	40 84
0.40 - 0.50	-							0			VOL	140	04
0.50 - 0.60			Solid ref	usal at	0.47m								
0.60 - 0.70													
0.70 - 0.80													
0.80 - 0.90													
0.90 - 1.00													
1.10 - 1.20													
1.20 - 1.30													
1.30 - 1.40													
1.40 - 1.50													
1.50 - 1.60													
1.00 - 1.70 1.70 - 1.80													
1.80 - 1.90													
1.90 - 2.00													
2.00 - 2.10													
2.10 - 2.20 2.20 - 2.30													
2.30 - 2.40													
2.40 - 2.50													
2.50 - 2.60													
2.60 - 2.70													
2.70 - 2.80 2.80 - 2.90													
2.90 - 3.00													
3.00 - 3.10													
3.10 - 3.20													
3.20 - 3.30													
3.40 - 3.50													
3.50 - 3.60													
3.60 - 3.70													
3.70 - 3.80													
3.80 - 3.90 3.90 - 4.00													
4.00 - 4.10													
4.10 - 4.20													
4.20 - 4.30													
4.30 - 4.40													
4.40 - 4.50 4.50 - 4.60													
4.60 - 4.00													
4.70 - 4.80													
4.80 - 4.90													
4.90 - 5.00													
Practical refusal = 1	Notes. Practical refusal = 25+ blows per 100mm "Solid" refusal = no further penetration and "solid" ringing sound from slide hammer												
** Insufficient data	to derive infe	erred para	meters				2000						
Refer to Information Sheets for Terms and Symbols DCP Log - Revision 17													





OF RS		
	APPROXIMATE ONL' SUBJECT TO DETAI SOURCE: "EZZY AF PLAN HOSIE-MURF 1 ISSUE G	Y – L SURVEY. RCHITECTS XAY-SHEET
	THIS DRAWING IS ILLUSTRATE TEST L ONLY, AND <u>MUST</u> <u>USED FOR ANY OT</u> <u>PURPOSE</u> . COPYRIC SOURCE DRAWING WITH EZZY ARCHIT	USED TO .OCATIONS <u>NOT BE</u> <u>HER</u> HT OF REMAINS ECTS
ERS LODGE		job no.:
IVE, THREDBO		2696
EDBO PTY LTD		fig: issue:
	CNECKED: MAB	2
	scale: 1:200 A3	