

Geotechnical Policy

Kosciuszko Alpine Resorts

Form 4 – Minimal Impact Certification

DA Number:

This form may be used where minor construction works which present minimal or no geotechnical impact on the site or related land are proposed to be erected within the "G" line area of the geotechnical maps.

A geotechnical engineer or engineering geologist must inspect the site and/or review the proposed development documentation to determine if the proposed development requires a geotechnical report to be prepared to accompany the development application. Where the geotechnical engineer determines that such a report is not required then they must complete this form and attach design recommendations where required. A copy of Form 4 with design recommendation, if required, must be submitted with the development application.

Please contact the Alpine Resorts Team in Jindabyne for further information - phone 02 6456 1733.

To complete this form, please place a cross in the appropriate boxes [] and complete all sections.

1. Declaration made by geotechnical engineer or engineering geologist in relation to a nil or minimal geotechnical impact assessment and site classification

AGI ZENON	
OF	
Company/organisation	
JK GEOTECHNICS	
have inspected the site and reviewed the repo-	+, fet: 27811 ++ 18 pf, dated 19/1/17, pepored by Adrian Hul
have inspected the site and Arenewed the repo- PROBSED FRONT VAL As a result of my site inspec (List of documentation reviewe	I reviewed the proposed development known as I, fiel: 27811 FH 18 pf, dated 19/117, perfored by Adrian Hul LEY EMATHWORKS, MITCHELL T-BAR LINE + CARPET- Stion and review of the following documentation d)
have inspected the site and reviewed the repo- PROBSED MONT VAL As a result of my site inspec (List of documentation reviewe · Statement o	I reviewed the proposed development known as 4, fet: 27811 FH 18 pf, dated 19/117, perfored by Adrian Hul LEY EMATHWOAKS, MITCHELL T-BAR LINE + CARPET- Sction and review of the following documentation 4 UNDAD id) f Environmentel Effects repurt, dated
have inspected the site and reviewed the repo- PROBSED MONT VAL As a result of my site inspect (List of documentation reviewe Statement of December 200	I reviewed the proposed development known as 4, Ref: 27811 HHIB rpt, dated 19/1117, performed by Adrian Hul LEY EMATHWOAKS, MITCHELL T-BAR LINE + CARPET- Sction and review of the following documentation 4 UNDAD Sction and review of the following documentation 4 UNDAD Sction and review of the following documentation 4 UNDAD Sction and review of the following documentation 4 UNDAD School of Adrian Hul School of Adrian Hul Sch
have inspected the site and reviewed the repo- PROBSED MONT VAL As a result of my site inspect (List of documentation reviewe Statement of December 200 Percenter 8/4	I reviewed the proposed development known as +, fut: 27811 fH18 pf, dated 19/117, perfored by Adrian Hul LEY EARTHWORKS, MITCHERL T-BAR LINE + CARPET- ction and review of the following documentation f Environmente Effects report, dated 16, prepared by Tanya Bishop of 0 fth Ltd
have inspected the site and revened the repo- PROBSED MONT VAL As a result of my site inspect (List of documentation reviewe · Statement of December 200 Perisher Blue	I reviewed the proposed development known as 4, fut: 27811 fH18 pf, dated 19/117, performed by Adrian Hul LEY EARTHWORKS, MITCHERL T-BARL LINE + CARPET- ction and review of the following documentation f Environmente Effects repurt, dated 16, prepared by Tanya Bishop of e Pty Ltd.
have inspected the site and reviewed the repo- PROBSED MONT VAL As a result of my site inspect (List of documentation reviewe · Statement or December 200 Perisher Blue	I reviewed the proposed development known as 4, Ref: 27811 FH18rpf, dated 19/1117, performed by Adrian Hul LEY EARTHWORKS, MITCHELL T-BAR LINE + CARPET- Sction and review of the following documentation 4 UNDAD Sction and review of the following documentation 5 UNDAD Sction and review of the following documentation 5 UNDAD 5 UND

Geotechnical Form 4 – Kosciuszko Alpine Resorts Department of Planning & Environment Page 1 of 2 Version: December 2015 I have determined that;

the current load-bearing capacity of the existing building will not be exceeded or adversely impacted by the proposed development, and

the proposed works are of such a minor nature that the requirement for geotechnical advice in the form of a geotechnical report, prepared in accordance with the "Policy", is considered unnecessary for the adequate and safe design of the structural elements to be incorporated into the new works, and

in accordance with AS 2870.1 Residential Slabs and Footings, the site is to be classified as a type

insert classification type)	
Class	

I have attached design recommendations to be incorporated in the structural design in accordance with this site classification.

I am aware that this declaration shall be used by the Department as an essential component in granting development consent for a structure to be erected within the "G" line area (as identified on the geotechnical maps) of Kosciuszko Alpine Resorts without requiring the submission of a geotechnical report in support of the development application.

2. Signatures

Signature	Chartered
When.	CP .
Name	Date
Agi Zenon	19/1

Chartered professional status

FIE ALST No. 2132971

3. Contact details

Alpine Resorts Team

Shop 5A, 19 Snowy River Avenue P O Box 36, JINDABYNE NSW 2627 Telephone: 02 6456 1733 Facsimile: 02 6456 1736 Email: alpineresorts@planning.nsw.gov.au

REPORT

TO PERISHER BLUE PTY LTD

ON GEOTECHNICAL ASSESSMENT

FOR PROPOSED FRONT VALLEY EARTHWORKS, MITCHELL T-BAR LINE AND CARPET 4 UNLOAD

AT PERISHER SKI RESORT, PERISHER VALLEY, NSW

> 19 January 2017 Ref: 27811RH18rpt

JK Geotechnics GEOTECHNICAL & ENVIRONMENTAL ENGINEERS

PO Box 976, North Ryde BC NSW 1670 Tel: 02 9888 5000 Fax: 02 9888 5003 www.jkgeotechnics.com.au

Jeffery & Katauskas Pty Ltd, trading as JK Geotechnics ABN 17 003 550 801





Date:19 January 2017Report No:27811RH18rptRevision No:0

Adn Hulf P.

Report prepared by:

Adrian Hulskamp Senior Associate | Geotechnical Engineer

Report reviewed by:

Agi Zenon Principal | Geotechnical Engineer

For and on behalf of JK GEOTECHNICS PO Box 976 NORTH RYDE BC NSW 1670

© Document Copyright of JK Geotechnics.

This Report (which includes all attachments and annexures) has been prepared by JK Geotechnics (JKG) for its Client, and is intended for the use only by that Client.

This Report has been prepared pursuant to a contract between JKG and its Client and is therefore subject to:

- a) JKG's proposal in respect of the work covered by the Report;
- b) the limitations defined in the Client's brief to JKG;
- c) the terms of contract between JK and the Client, including terms limiting the liability of JKG.

If the Client, or any person, provides a copy of this Report to any third party, such third party must not rely on this Report, except with the express written consent of JKG which, if given, will be deemed to be upon the same terms, conditions, restrictions and limitations as apply by virtue of (a), (b), and (c) above.

Any third party who seeks to rely on this Report without the express written consent of JKG does so entirely at their own risk and to the fullest extent permitted by law, JKG accepts no liability whatsoever, in respect of any loss or damage suffered by any such third party.

At the Company's discretion, JKG may send a paper copy of this report for confirmation. In the event of any discrepancy between paper and electronic versions, the paper version is to take precedence. The USER shall ascertain the accuracy and the suitability of this information for the purpose intended; reasonable effort is made at the time of assembling this information to ensure its integrity. The recipient is not authorised to modify the content of the information supplied without the prior written consent of JKG.



TABLE OF CONTENTS

1	INTRODUCTION	1
2	ASSESSMENT PROCEDURE	2
3	SITE OBSERVATIONS	2
4	COMMENTS AND RECOMMENDATIONS	3
5	GENERAL COMMENTS	5

SITE LOCATION PLAN (BASED ON APPENDIX B IN SUPPLIED SEE REPORT)



1 INTRODUCTION

This report presents the results of a geotechnical assessment for the proposed Front Valley earthworks, Mitchell T-bar line and Carpet 4 Unload at Perisher Ski Resort, Perisher Valley, NSW. The assessment was commissioned by Mr Andrew Kennedy of Perisher Blue Pty Ltd (PB).

Based on the supplied Statement of Environmental Effects (SEE) report prepared by Tanya Bishop of PB dated January 2017, we understand that the proposed works will comprise the following:

- 1. Placement and compaction of a fill embankment between Towers 1 & 2 of Mitchell T-bar over a footprint 50m long by 6m wide. The fill will be placed to a maximum depth of 1.5m above existing grade. The north-western, south-eastern and south-western sides of the fill will be battered to a gentle slope to match existing levels. The fill on its north-eastern side will be supported by large rocks i.e. the rocks will act as a retaining structure.
- 2. A fauna crossing will be constructed towards the south-eastern end and will extend through the fill embankment via 225mm pipe.
- 3. Minor regrading of the existing ground surface at the north-western end of Ski Carpet 4 over a footprint 7m long by 7m wide.

We understand that the main purpose of the fill is to reduce the amount of snow that is required in the area during the ski season. The proposed works are shown on the attached Figure 1, which is based on the figure presented in Appendix B of the supplied SEE report.

The purpose of the geotechnical assessment was to review the supplied SEE report and to determine whether the proposed works present minimal or no geotechnical impact on the site, and if so, to complete a signed Form 4 – Minimal Impact Certification. Based on our assessment, we would determine whether a further geotechnical report, which includes a risk assessment, would be required.

This report has been prepared in accordance with the requirements of the Geotechnical Policy for Kosciuszko Alpine Resorts (2003).



2 ASSESSMENT PROCEDURE

The assessment included a walkover inspection of the topographic, surface drainage and geological conditions of the site and its immediate environs by our Senior Associate Geotechnical Engineer (Adrian Hulskamp) on 15 November 2016, as well as a review of the supplied SEE report.

A subsurface investigation, geotechnical laboratory testing and a contamination screen of site soils and groundwater were outside the agreed scope of this assessment.

3 SITE OBSERVATIONS

The site is located towards the toe of a south facing hillside, which grades between approximately 5° and 15°.

At the time of our walkover inspection, the ground surface over the footprint of the proposed fill embankment was uneven and mostly grass covered. There appeared to have been fill placed in the area to a maximum height of approximately 1m where the new fill is proposed. A relatively flat 'bog' area was located to the north-west of the proposed fill embankment footprint. Refer to Plate 1 below.



Plate 1: View looking upslope to the north-west showing area of proposed fill embankment.

We did not observe any obvious signs of hillside instability, such as tension cracks, slumping etc. Further, we did not observe any obvious signs of instability of the existing fill batters.



The drainage conditions across the hillside were generally good, apart from the adjacent 'bog' area.

4 COMMENTS AND RECOMMENDATIONS

Based on our review of the supplied SEE report, the relatively shallow depth of fill to be placed and the gentle ground slopes over the footprint of the proposed fill embankment, we consider that the proposed works will constitute 'minimal or no geotechnical impact' on the site. Therefore, we consider that a geotechnical report prepared in accordance with the Geotechnical Policy for Kosciuszko Alpine Resorts (2003) is not required. Our current report is preceded by the completed Form 4 – Minimal Impact Certification.

As the site appears to be underlain by some existing fill which is expected to be 'uncontrolled', the site is Class 'P', in accordance with AS2870-2011 'Residential slabs and footings'.

We recommend that the following advice be taken into account during the design and construction phase:

Earthworks

- Initially, all grass, vegetation, root affected soils and any topsoil should be stripped from the footprint of the proposed fill embankment. These materials must be disposed appropriately off site, or alternatively used for landscaping purposes within the ski resort.
- Following the above, the exposed subgrade should be inspected by a geotechnical engineer to assess whether proof rolling of the subgrade is warranted, prior to filling. The objective of the proof rolling is to assist with the detection of any 'soft' or 'unstable' subgrade.
- The fill should be placed as engineered fill so as to reduce the potential for the fill to erode after it has been placed due to surface water runoff and to reduce post construction settlements. The fill material should comprise a high quality granular material, such as weathered granite or crushed imported granite sourced from the ski resort. The fill material must be 'clean', free of organic matter and have a particle size no greater than 75mm.
- The fill should be compacted in maximum 200mm thick loose layers to achieve a minimum density ratio of 95% of Standard Maximum Dry Density (SMDD). If compaction is carried out using a roller attachment fitted to an excavator or a small roller, then thinner loose layers may need to be placed to achieve sufficient compaction. Further, if the loose layer thickness is less than 200mm, the maximum particle size must reduce to no larger than one third of the loose layer thickness.

- Density tests should be carried out on the fill to assess that sufficient compaction has been achieved. The testing frequency should be as per the requirements of Table 8.1 in AS3798-2007. We recommend at least Level 2 control of fill compaction be adhered to.
- We recommend that the fill extend a horizontal distance of at least 1m beyond the design fill embankment slope (with exception of the north-eastern side where the retaining wall is proposed) so that adequate edge compaction can be achieved. On completion of filling, the excess fill can be trimmed back to form the required batter slopes, which must not be steeper than 1 Vertical (V) in 2 Horizontal (H) in the permanent case.
- The fill batters should be protected from erosion by re-establishing a grass cover, apart from the north-eastern side of the fill embankment which will be supported by large rocks (refer to section below).

Proposed Retaining Wall (Placement of Large Rocks)

We recommend the following for the proposed rock retaining wall:

- The rocks should be founded in competent residual soils of least very stiff strength and/or weathered granite bedrock. The embedment of the rocks must be at least 0.1m into weathered granite bedrock or at least 0.5m into soil. If there is any doubt as to the quality of the foundation material, particularly given the proximity of the 'bog' area to the north-east, then further geotechnical advice should be sought.
- Assuming a maximum retained height of 1.5m and a horizontal backfill surface, the width of the rock retaining wall over its base must be at least 1m and at least 0.5m wide at its crest, provided the face is graded no steeper than 2V in 1H.
- The rock retaining wall should have a free draining backfill material directly behind the rocks and measures taken to provide complete and permanent drainage of the ground behind the wall. Subsurface drains should incorporate a non-woven geotextile fabric (eg. Bidim A34) to act as a filter against subsoil erosion.
- The rocks should comprise sound and durable granite of at least high strength, or other rock approved by the geotechnical engineer.
- The rocks must be placed in such a manner that they are stable, they interlock and are laid on their broadest base.



5 GENERAL COMMENTS

The recommendations presented in this report include specific issues to be addressed during the construction phase of the project. In the event that any of the construction phase recommendations presented in this report are not implemented, the general recommendations may become inapplicable and JK Geotechnics accept no responsibility whatsoever for the performance of the structure where recommendations are not implemented in full and properly tested, inspected and documented.

It is possible that the subsurface soil, rock or groundwater conditions encountered during construction may be found to be different (or may be interpreted to be different) from those expected. Also, we have not had the opportunity to observe surface run-off patterns during heavy rainfall and cannot comment directly on this aspect. If conditions appear to be at variance or cause concern for any reason, then we recommend that you immediately contact this office.

This report provides advice on geotechnical aspects for the proposed civil and structural design. As part of the documentation stage of this project, Contract Documents and Specifications may be prepared based on our report. However, there may be design features we are not aware of or have not commented on for a variety of reasons. The designers should satisfy themselves that all the necessary advice has been obtained. If required, we could be commissioned to review the geotechnical aspects of contract documents to confirm the intent of our recommendations has been correctly implemented.

This report has been prepared for the particular project described and no responsibility is accepted for the use of any part of this report in any other context or for any other purpose. If there is any change in the proposed development described in this report then all recommendations should be reviewed. Copyright in this report is the property of JK Geotechnics. We have used a degree of care, skill and diligence normally exercised by consulting engineers in similar circumstances and locality. No other warranty expressed or implied is made or intended. Subject to payment of all fees due for the assessment, the client alone shall have a licence to use this report. The report shall not be reproduced except in full.

Appendix B -Site Environmental Management Plan (SEMP)





SITE LOCATION PLAN