



Planning & Environment


Issued under the Environmental Planning and Assessment Act 1979

Approved Application No. DA 9841

granted on the 11 OCT 2019

Signed MB

Sheet No. 7 of 19



This drawing should be read in conjunction with all relevant contracts, specifications and drawings. Dimensions are in millimetres. Levels are metres. Do not scale off drawings. Use figured dimensions only. Check dimensions on Site. Report discrepancies immediately.



NOTES

AUTHORISED FOR ISSUE

D	04/01/19	DA RE-ISSUE	ST
C	18/12/18	DA RE-ISSUE	SM
B	13/12/18	DEVELOPMENT APPLICATION ISSUE	ST
A	23/11/18	INITIAL ISSUE	ST

ISSUE	DATE	SUBJECT	VALID'D
-------	------	---------	---------

CLIENT

EVENT Hospitality and Entertainment

DEVELOPMENT APPLICATION

PROJECT  
FRIDAY FLAT CARPARK CP2

Friday Drive  
Thredbo Village

ARCHITECT

**djrd** architects

T + 612 9319 2955  
 ABN: 48 942 921 969  
 Nominated Architects:  
 Andrew Hipwell 6562  
 Daniel Beekwilder 6192

64 Rose Street  
 Chippendale NSW 2008  
 Sydney Australia  
 djrd.com.au

DRAWN	SCALE AT A3
ST	1:2000

DESCRIPTION  
 COVER PAGE AND LOCATION PLAN

PROJECT No	DRAWING No	REVISION
18 420	A0.100	D

# FRIDAY FLAT CARPARK CP2 DEVELOPMENT APPLICATION

## DRAWING LIST

DWG #	REV	DATE	DRAWING TITLE
A0.100	D	04/01/19	COVER PAGE AND LOCATION PLAN
A0.150	C	04/01/19	SITE ANALYSIS PLAN
A0.200	C	04/01/19	REHABILITATION AND LANDSCAPE CONCEPT PLAN
A1.100	D	04/01/19	GENERAL ARRANGEMENT PLAN
A2.500	B	04/01/19	INDICATIVE SECTION & CAR SPACE DETAIL



EXISTING SUB-ALPINE WOODLAND




Planning & Environment

Issued under the Environmental Planning and Assessment Act 1979

Approved Application No. DA 9841

granted on the 11 OCT 2019

Signed M.B. of 19  
Sheet No. 9 of 19



This drawing should be read in conjunction with all relevant contracts, specifications and drawings. Dimensions are in millimetres. Levels are metres. Do not scale off drawings. Use figured dimensions only. Check dimensions on Site. Report discrepancies immediately.

NOTES

AUTHORISED FOR ISSUE

ISSUE	DATE	SUBJECT	VALID
C	04/01/19	UPDATED PLAN	ST
B	18/12/18	DA RE-ISSUE	SM
A	13/12/18	DEVELOPMENT APPLICATION ISSUE	ST

CLIENT

EVENT Hospitality and Entertainment

DEVELOPMENT APPLICATION

PROJECT: FRIDAY FLAT CARPARK CP2

Friday Drive  
Dredbo Village

ARCHITECT

**djrd** architects  
T +612 9319 2955  
ABN: 48 942 921 969  
Nominated Architects:  
Andrew Hipwell 6562  
Daniel Beekwilder 6192  
64 Rose Street  
Chippendale NSW 2008  
Sydney Australia  
djrd.com.au

LEGEND

- EXTENT OF AREAS DISTURBED DURING CONSTRUCTION TO BE REVEGETATED + STABILISED. MAX 1.5m BANKS MADE GOOD WITH SITE TOPSOIL / FIXED IN PLACE WITH 'SOIL SAVING' JUTE FABRIC / 100% FESCUE SEEDING OVERPLANTED WITH SNOWGRASS CELLS + INDIVIDUAL TREE + SHrub PLANTINGS GROUPED AROUND BOULDERS.
- ROCK WALLING TO 1.5-2.0m MAX HEIGHT BLENDED INTO ADJACENT PROFILES WITH SITE BOULDERS WON FROM EXCAVATION / REFER ENGINEERING DETAIL
- PROPOSED GRAVEL PATH TO LINK EXISTING BIKE + PEDESTRIAN TRAILS WINTER ACCESS FROM CARPARK / SUMMER BIKING ACCESS.
- CATCH DRAINS TO TOP OF BANKS

- INDICATIVE PLANTING ALLOWANCE
- 10 EUC. PAUCIFLORA NIPHOPHILA
  - 15 EUC. STELLATA
  - 20 GREVILLEA VICTORIANAE
  - 150 DIANEUA TAZMANICA
  - 500 POA PANCRETIAE (SNOWGRASS CELLS)
- NOTE: SUPPLY FROM APPROVED GROWERS.


- ALL AREAS DISTURBED DURING CONSTRUCTION TO BE STABILISED + MADE GOOD / REFER 'SEMP' + 'SEE'
- ALL REVEG TO BE MULCHED FROM BENCH CHIPPINGS WON FROM APPROVED VEGETATION REMOVAL
- SITE PROTECTION MEASURES AS PER 'SEMP'
- REFER ARCH + ENGINEERING DETAIL

NSW GOVERNMENT  
Planning & Infrastructure


11 JAN 2019

DEVELOPMENT ASSESSMENT AND SYSTEMS PERFORMANCE RECEIVED - JINDABYNE

DRAWN: Author  
SCALE: AT A3  
DESCRIPTION: REHABILITATION AND LANDSCAPE CONCEPT PLAN  
PROJECT No: 18 420  
DRAWING No: A0.200  
REVISION: C



**1 GENERAL ARRANGEMENT PLAN WEST**  
1 : 500



**2 GENERAL ARRANGEMENT PLAN EAST**  
1 : 500

**PARKING SCHEDULE**

95 NEW CP2 PARKING SPACES
88 EXISTING FRIDAY DRIVE PARKING SPACES
72 REVISED FRIDAY DRIVE PARKING SPACES FOLLOWING CP2 (INC. RAMPS)
79 NET ADDITIONAL PARKING SPACES

NSW GOVERNMENT  
Planning & Infrastructure

11 JAN 2019

DEVELOPMENT ASSESSMENT AND SYSTEMS PERFORMANCE RECEIVED - JINDABYNE

NSW GOVERNMENT Planning & Environment

Issued under the Environmental Planning and Assessment Act 1979

Approved Application No. DA 9841

granted on the 11 OCT 2019

Signed [Signature]

Sheet No. 10 of 19

This drawing should be read in conjunction with all relevant contracts, specifications and drawings. Dimensions are in millimetres. Levels are metres. Do not scale off drawings. Use figured dimensions only. Check dimensions on Site. Report discrepancies immediately.

NOTES

AUTHORISED FOR ISSUE

ISSUE	DATE	SUBJECT	VALID'D
D	04/01/19	UPDATED PLAN	ST
C	18/12/18	DA RE-ISSUE	SM
B	13/12/18	DEVELOPMENT APPLICATION ISSUE	ST
A	23/11/18	INITIAL ISSUE	ST

CLIENT  
EVENT Hospitality and Entertainment

DEVELOPMENT APPLICATION  
PROJECT  
FRIDAY FLAT CARPARK CP2


Friday Drive  
Thredbo Village

ARCHITECT  
**djrd architects**  
T + 612 9319 2955  
ABN: 48 942 921 969  
Nominated Architects:  
Andrew Hipwell 6562  
Daniel Beekwilder 6192  
64 Rose Street  
Chippendale NSW 2008  
Sydney Australia  
djrd.com.au

DRAWN  
Author As indicated

DESCRIPTION  
GENERAL ARRANGEMENT PLAN

PROJECT No	DRAWING No	REVISION
18 420	A1.100	D



**1 INDICATIVE SECTION**  
A1.100 1:100

This drawing should be read in conjunction with all relevant contracts, specifications and drawings. Dimensions are in millimetres. Levels are metres. Do not scale off drawings. Use figured dimensions only. Check dimensions on Site. Report discrepancies immediately.

NOTES

AUTHORISED FOR ISSUE

B	04/01/19	UPDATED PLAN	ST
A	18/12/18	DA RE-ISSUE	SM

ISSUE DATE SUBJECT VALIDN.

CLIENT  
EVENT Hospitality and Entertainment

DEVELOPMENT APPLICATION  
PROJECT  
FRIDAY FLAT CARPARK CP2

Friday Drive  
Thredbo Village

ARCHITECT  
**djrd** architects  
T + 612 9319 2955  
ABN: 48 942 921 969  
Nominated Architects:  
Andrew Hipwell 6562  
Daniel Beekwilder 6192  
64 Rose Street  
Chippendale NSW 2008  
Sydney Australia  
djrd.com.au

**NSW GOVERNMENT** Planning & Environment  
Issued under the Environmental Planning and Assessment Act 1979


Approved Application No. **DA 9841**

granted on the **11 OCT 2019**

Signed **MB**

Sheet No. **11** of **19**

**NSW GOVERNMENT** Planning & Infrastructure  
**11 JAN 2019**  
DEVELOPMENT ASSESSMENT AND SYSTEMS PERFORMANCE RECEIVED - JINDABYNE



**2 CAR SPACE DETAIL**  
1:100

DRAWN SCALE AT A3  
Author 1:100

DESCRIPTION  
INDICATIVE SECTION & CAR SPACE DETAIL

PROJECT No	DRAWING No	REVISION
18 420	A2.500	B

# THREDBO ALPINE RESORT CAR PARK 2



Planning & Environment

Issued under the Environmental Planning and Assessment Act 1979

Approved Application No. DA 9841

granted on the 11 OCT 2019

Signed M.B.

Sheet No. 12 of 19


**GENERAL NOTES**

- Contractor must verify all dimensions and existing levels on site prior to commencement of works. Any discrepancies to be reported to the Engineer.
- Strip of topsoil from the construction area. All stripped topsoil shall be disposed of off-site unless directed otherwise.
- Make smooth connection with all existing works.
- Compact subgrade under buildings and pavements to minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1. Compaction under buildings to extend 2m minimum beyond building footprint.
- All work on public property, property which is to become public property, or any work which is to come under the control of the Statutory Authority, the Contractor is to ensure that the drawings used for construction have been approved by all relevant authorities prior to commencement site.
- All work on public property, property which is to become public property, or any work which is to come under the control of the Statutory Authority is to be carried out in accordance with the requirements of the relevant Authority. Where the requirements of the Authority are different to the drawings and specifications, the requirements of the Authority shall be applicable.
- For all temporary barriers refer to geotechnical recommendations.

**KERBING NOTES**

Includes all kerbs, gutters, dish drains, crossings and edges.

- All kerbs, gutters, dish drains and crossings to be constructed on minimum 75mm granular basecourse compacted to minimum 98% modified maximum dry density in accordance with AS 1289 5.2.1.
- Expansion joints (EJ) to be formed from 10mm compressible cork filler board for the full depth of the section and cut to profile. Expansion joints to be located at drainage pits, on tangent points of curves and elsewhere at 12m centres except for integral kerbs where the expansion joints are to match the joint locations in slabs.
- Weakened plane joints to be min 3mm wide and located at 3m centres except for integral kerbs where weakened plane joints are to match the joint locations in slabs.
- Broomed finished to all ramped and vehicular crossings, all other kerbing or dish drains to be steel foot finished.
- In the replacement of kerbs - Existing road pavement is to be sawcut 900mm from lip of gutter. Upon completion of new kerbs, new basecourse and surface is to be laid 900mm wide to match existing materials and thicknesses. Existing drainage pipes are to be built into the new kerb with a 100mm dia hole. Existing kerbs are to be completely removed where new kerbs are shown.



**EROSION AND SEDIMENT CONTROL NOTES**

- All work shall be generally carried out in accordance with:
  - Local authority requirements,
  - EPA - Pollution control manual for urban stormwater,
  - LANDCOM NSW - Managing Urban Stormwater: Soils and Construction ("Blue Book").
- Erosion and sediment control drawings and notes are provided for the whole of the works. Should the Contractor stage these works then the design may be required to be modified. Variation to these details may require approval by the relevant authorities. The erosion and sediment control plan shall be implemented and adapted to meet the varying situations as work on site progresses. Maintain all erosion and sediment control devices to the satisfaction of the superintendent and the local authority.
- When stormwater pits are constructed prevent silt runoff entering the pits unless silt fences are erected around pits.
- Minimise the area of site being disturbed at any one time.
- Protect all stockpiles of materials from scour and erosion. Do not stockpile loose material in roadways, near drainage pits or in watercourses.
- All soil and water control measures are to be put back in place at the end of each working day, and modified to best suit site conditions.
- Control water from upstream of the site such that it does not enter the disturbed site.
- All construction vehicles shall enter and exit the site via the temporary construction entry/exit.
- All vehicles leaving the site shall be cleaned and inspected before leaving.
- Maintain all stormwater pipes and pits clear of debris and sediment. Inspect stormwater system and clean out after each storm event.
- Clean out all erosion and sediment control devices after each storm event.

**Sequence Of Works**

- Prior to commencement of excavation the following soil management devices must be installed.
  - Construct silt fences below the site and across all potential runoff sites.
  - Construct temporary construction entry/exit and divert runoff to suitable control systems.
  - Construct measures to divert upstream flows into existing stormwater system.
  - Construct sedimentation traps/basins including outlet control and overflow.
  - Construct turf lined swales.
  - Provide sandbag sediment traps upstream of existing pits.
  - Construct geotextile filter pit surround around all proposed pits as they are constructed.
- On completion of pavement provide sand bag inlet sediment traps around pits.
- Provide and maintain a strip of turf on both sides of all roads after the construction of kerbs.

**BULK EARTHWORKS NOTES**

- All bulk earthworks setout from grid lines U.N.O.
- All batterers at a slope of 2 (H) : 1 (V) U.N.O.
- Excavated material may be used as structural fill provided,
  - it complies with the specification requirements for fill material,
  - the placement moisture content complies with the Geotechnical Consultants requirements, and allows filling to be placed and profiled in accordance with the specification. Where necessary the Contractor must moisture condition the excavated material to meet these requirements.
- Compact fill areas and subgrade to not less than:
 

Location	Standard dry density (AS 1289 5.1.1)	Moisture (OMC)
Under building slabs on ground:	98%	±2%
Under roads and carparks:	98%	±2%
Landscape areas:	95%	±2%
- Before placing fill, proof roll exposed subgrade with a 10 tonne minimum roller to test subgrade and then remove soft spots (areas with more than 3mm movement under roller). Soft spots to be replaced with select fill U.N.O.
- Contractor shall place safety barriers around excavations in accordance with relevant safety regulations.
- For interpretation of bulk earthworks foot print line shown on the bulk earthworks drawings refer to the bulk earthworks construction legend.
- Bulk earthwork drawings are not to be used for detailed excavation.
- Refer to Geotechnical Report prepared by - DOUGLAS PARTNERS PROJECT 91329.00

**SAFETY IN DESIGN**

Contractor to refer to Appendix B of the Civil Specification for the Civil Risk and Solutions Register.

**EXISTING SERVICES**

Contractor to be aware existing services are located within the site. Location of all services to be verified by the Contractor prior to commencing works. Contractor to confirm with relevant authority regarding measures to be taken to ensure services are protected or procedures are in place to demolish or / or relocate.

**EXISTING STRUCTURES**

Contractor to be aware existing structures may exist within the site. To prevent damage to existing structures (s) and / or personnel, site works to be carried out as far as practicable from existing structures.

**EXISTING TREES**

Contractor to be aware existing trees exist within the site which need to be protected. To prevent damage to trees and / or personnel, site works to be carried out as far as practicable from existing trees. Advice needs to be sought from Arborist and / or Landscape Architect on measures required to protect trees.

**GROUNDWATER**

Contractor to be aware ground water levels are close to existing surface level. Temporary de-watering may be required during construction works.

**EXCAVATIONS**

Deep excavations due to stormwater drainage works is required. Contractor to ensure safe working procedures are in place for works. All excavations to be fenced off and batterers adequately supported to approval of Geotechnical Engineer.

**GROUND CONDITIONS**

Contractor to be aware of the site geotechnical conditions. Refer to geotechnical report by Douglas Partners (ref:91329) for details.

**HAZARDOUS MATERIALS**

Existing asbestos products & contaminated material may be present on site. Contractor to ensure all hazardous materials are identified prior to commencing works. Safe working practices as per relevant authority to be adopted and appropriate PPE to be used when handling all hazardous materials. Refer to geotechnical/environmental report by Douglas Partners (ref:91329) for details.

**CONFINED SPACES**

Contractor to be aware of potential hazards due to working in confined spaces such as stormwater pits, trenches and / or tanks. Contractor to provide safe working methods and use appropriate PPE when entering confined spaces.

**MANUAL HANDLING**

Contractor to be aware manual handling may be required during construction. Contractor to take appropriate measures to ensure manual handling procedures and assessments are in place prior to commencing works.

**WATER POLLUTION**


Contractor to ensure appropriate measures are taken to prevent pollutants from construction works contaminating the surrounding environment.

**SITE ACCESS/EGRESS**

Contractor to be aware site works occur in close proximity to footpaths and roadways. Contractor to erect appropriate barriers and signage to protect site personnel and public.

**VEHICLE MOVEMENT**

Contractor to supply and comply with traffic management plan and provide adequate site traffic control including a certified traffic marshal to supervise vehicle movements where necessary.







**REFERENCE DRAWINGS**

- These drawings have been based from, and to be read in conjunction with the following Consultants drawings. Any conflict to the drawings must be notified immediately to the Engineer.

Consultant	Dwg Title	Dwg No	Rev	Date
djd	FLAT FRIDAY LAYOUT SURVEY HORIZONTAL	A-10.100	B	03.10.18
				30.07.18

**CONCRETE FINISHING NOTES**

- All exposed concrete pavements are to be broomed finished.
- All edges of the concrete pavement including keyed and dowelled joints are to be finished with an edging tool.
- Concrete pavements with grades greater than 10% shall be heavily broomed finished.
- Carbondurum to be added to all stair treads and ramped crossings U.N.O.



**PIT SCHEDULE**

Note: Grate size does not necessarily reflect pit size, refer pit type details, shown on detail sheets - 7  
Final internal pit dimensions are to comply with AS3500

Type	Description	Cover (Clear Opening)	Number
A	Detention outlet pit	900 x 900 Class C galvanised mild steel grate hinged to frame with trash screen	1

**SURVEY AND SERVICES INFORMATION SURVEY**

Origin of levels : TBC  
Datum of levels : A.H.D. AUSTRALIAN HEIGHT DATUM  
Coordinate system : TBC  
Survey prepared by : TBC  
Setout Points : CONTACT THE SURVEYOR

Taylor Thomson Whitting does not guarantee that the survey information shown on these drawings is accurate and will accept no liability for any inaccuracies in the survey information provided to us from any cause whatsoever.

**UNDERGROUND SERVICES - WARNING**

The locations of underground services shown on Taylor Thomson Whittings drawings have been plotted from diagrams provided by service authorities. This information has been prepared solely for the authorities own use and may not necessarily be updated or accurate.


The position of services as recorded by the authority at the time of installation may not reflect changes in the physical environment subsequent to installation.

Taylor Thomson Whitting does not guarantee that the services information shown on these drawings shows more than the presence or absence of services, and will accept no liability for inaccuracies in the services information shown from any cause whatsoever.

The Contractor must confirm the exact location and extent of services prior to construction and notify any conflict with the drawings immediately to the Engineer/Superintendent.

The contractor is to get approval from the relevant state survey department, to remove/adjust any survey mark. This includes but is not limited to: State Survey Marks (SSM), Permanent Marks (PM), cadastral reference marks or any other survey mark which is to be removed or adjusted in any way.

Taylor Thomson Whitting plans do not indicate the presence of any survey mark. The contractor is to undertake their own search.




**RETAINING WALLS**

- Drainage shall be provided as shown on the drainage drawings.
- Backfilling shall be carried out after gravel or concrete has reached a minimum strength of 0.85 fc. Backfilling shall be approved granular material compacted in layers not exceeding 200mm to 95% Standard compaction unless noted otherwise.
- Provide waterproofing to back of walls as specified or noted.
- Where retaining walls rely on connecting structural elements for stability, do not backfill against the wall unless it is adequately propped or the elements have been constructed and have sufficient strength to withstand the loads.
- For all temporary batterers obtain geotechnical engineers recommendations.

**REINFORCED EARTH WALL NOTE**

- All masonry blocks and gabion baskets are to the manufacturer's specification.
- Geofabric type and length is to be laid as per plans.
- Subgrade bearing tests must be completed and results reviewed prior to gabion basket laying.
- Contractor to submit shear box test results to ensure adequate friction angle, unit weight and cohesion.
- Contractor must provide test records to ensure compaction results and moisture content between layers that have been specified is achieved.
- Soil conditions are anticipated as noted by the latest geotechnical report. Any conflicts or changes with the soil conditions or design, the contractor is to seek approval for any changes by the geotechnical engineer.





NSW GOVERNMENT  
Planning & Infrastructure

11 JAN 2019

DEVELOPMENT ASSESSMENT AND SYSTEMS PERFORMANCE RECEIVED - JINDABYNE

File Name: C:\G0000000 - USBC - drawings - Plot File Created: Jan 10, 2019 - 1:27pm



**NSW GOVERNMENT** | **Planning & Environment**  
 Issued under the Environmental Planning and Assessment Act 1979  
 Approved Application No. **DA 9841**  
 granted on the **11 OCT 2019**  
 Signed **MS**  
 Sheet No. **13** of **19**

**EROSION AND SEDIMENT CONTROL NOTES**





- All work shall be generally carried out in accordance with (A) Local authority requirements, (B) EPA - Pollution control manual for urban stormwater, (C) LANDCOM NSW - Managing Urban Stormwater: Soils and Construction ("Blue Book").
- Erosion and sediment control drawings and notes are provided for the whole of the works. Should the Contractor stage these works then the design may be required to be modified. Variation to these details may require approval by the relevant authorities. The erosion and sediment control plan shall be implemented and adopted to meet the varying situations as work on site progresses.
- Maintain all erosion and sediment control devices to the satisfaction of the superintendent and the local authority.
- When stormwater pits are constructed prevent site runoff entering the pits unless silt fences are erected around pits.
- Minimise the area of site being disturbed at any one time.
- Protect all stockpiles of materials from scour and erosion. Do not stockpile loose material in roadways, near drainage pits or in watercourses.
- All soil and water control measures are to be put back in place at the end of each working day, and modified to best suit site conditions.
- Control water from upstream of the site such that it does not enter the disturbed site.
- All construction vehicles shall enter and exit the site via the temporary construction entry/exit.
- All vehicles leaving the site shall be cleaned and inspected before leaving.
- Maintain all stormwater pipes and pits clear of debris and sediment. Inspect stormwater system and clean out after each storm event.
- Clean out all erosion and sediment control devices after each storm event.

**Sequence Of Works**

- Prior to commencement of excavation the following soil management devices must be installed.
  - Construct silt fences below the site and across all potential runoff sites.
  - Construct temporary construction entry/exit and divert runoff to suitable control systems.
  - Construct measures to divert upstream flows into existing stormwater system.
  - Construct sedimentation traps/basin including outlet control and overflow.
  - Construct turf lined swales.
  - Provide sandbag sediment traps upstream of existing pits.
- Construct geotextile filter pit surround around all proposed pits as they are constructed.
- On completion of pavement provide sand bag kerb inlet sediment traps around pits.
- Provide and maintain a strip of turf on both sides of all roads after the construction of kerbs.

**NSW GOVERNMENT**  
 Planning & Infrastructure  
**11 JAN 2019**  
 DEVELOPMENT ASSESSMENT AND SYSTEMS PERFORMANCE RECEIVED - JINDABYNE


**EROSION AND SEDIMENT CONTROL LEGEND**





**DA SUBMISSION**

P2 DA SUBMISSION		EC	JW	19.12.18	Client		Civil Engineer		Project		Sheet Subject		Scale: A1	Drawn	Authorised
P1 DA SUBMISSION		EC	JW	18.12.18	Client		Taylor Thomson Whitting		THREDBO ALPINE RESORT FRIDAY FLAT CAR PARKS		EROSION AND SEDIMENT CONTROL PLAN - CAR PARK 2		1:1000	HM	SB
Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date	Job No		Revision	Plot File Created: Dec 21, 2018 - 1:04pm		
										181487		C501	P2		


Filename: C501.dwg - User: duncan - Plot File Created: Dec 21, 2018 - 1:04pm





**NSW Government**  
**Planning & Environment**  
 Issued under the Environmental Planning and Assessment Act 1979  
 Approved Application No. DA 9841  
 granted on the 11 OCT 2019  
 Signed MB  
 Sheet No. 14 of 19


**NSW GOVERNMENT**  
**Planning & Infrastructure**  
 11 JAN 2019  
 DEVELOPMENT ASSESSMENT AND  
 SYSTEMS PERFORMANCE  
 RECEIVED - JINDABYNE


**DA SUBMISSION**

<table border="1"> <tr> <th>Rev</th> <th>Description</th> <th>Eng</th> <th>Draft</th> <th>Date</th> <th>Rev</th> <th>Description</th> <th>Eng</th> <th>Draft</th> <th>Date</th> </tr> <tr> <td>P5</td> <td>DA SUBMISSION</td> <td>DU</td> <td>JW</td> <td>07.01.19</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>P4</td> <td>DA SUBMISSION</td> <td>EC</td> <td>JW</td> <td>21.12.18</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>P3</td> <td>DA SUBMISSION</td> <td>EC</td> <td>JW</td> <td>20.12.18</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>P2</td> <td>DA SUBMISSION</td> <td>EC</td> <td>JW</td> <td>19.12.18</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>P1</td> <td>DA SUBMISSION</td> <td>EC</td> <td>JW</td> <td>18.12.18</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date	P5	DA SUBMISSION	DU	JW	07.01.19						P4	DA SUBMISSION	EC	JW	21.12.18						P3	DA SUBMISSION	EC	JW	20.12.18						P2	DA SUBMISSION	EC	JW	19.12.18						P1	DA SUBMISSION	EC	JW	18.12.18						Client Civil Engineer  612 9439 7288   48 Chandos Street St Leonards NSW 2065	Project <b>THREDBO ALPINE RESORT          FRIDAY FLAT CAR PARKS</b>	Sheet Subject <b>SITWORKS PLAN SHEET 1</b>	Scale: A1 1:300 Job No 181487 Plot File Created: Jan 10, 2019 - 2:01pm	Drawn WW Drawing No C502 Authorised SB Revision P5
Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date																																																								
P5	DA SUBMISSION	DU	JW	07.01.19																																																													
P4	DA SUBMISSION	EC	JW	21.12.18																																																													
P3	DA SUBMISSION	EC	JW	20.12.18																																																													
P2	DA SUBMISSION	EC	JW	19.12.18																																																													
P1	DA SUBMISSION	EC	JW	18.12.18																																																													






Chainage 0+190.00



Chainage 0+150.00



Chainage 0+060.00

**NSW GOVERNMENT** | **Planning & Environment**  
 Issued under the Environmental Planning and Assessment Act 1979  
 Approved Application No. DA 9841  
 granted on the 11 OCT 2019  
 Signed MS  
 Sheet No. 16 of 19

**NSW GOVERNMENT**  
 Planning & Infrastructure  
**11 JAN 2019**  
 DEVELOPMENT ASSESSMENT AND  
 SYSTEMS PERFORMANCE  
 RECEIVED - JINDABYNE

Filename: C505.dwg - USER: alexan - Plot File Created: Jan 10, 2019 - 2:10pm

<table border="1"> <tr> <td>P3</td> <td>DA SUBMISSION</td> <td>EC</td> <td>JW</td> <td>10.01.18</td> </tr> <tr> <td>P2</td> <td>DA SUBMISSION</td> <td>EC</td> <td>JW</td> <td>20.12.18</td> </tr> <tr> <td>P1</td> <td>DA SUBMISSION</td> <td>EC</td> <td>JW</td> <td>18.12.18</td> </tr> <tr> <td>Rev</td> <td>Description</td> <td>Eng</td> <td>Draft</td> <td>Date</td> </tr> </table>			P3	DA SUBMISSION	EC	JW	10.01.18	P2	DA SUBMISSION	EC	JW	20.12.18	P1	DA SUBMISSION	EC	JW	18.12.18	Rev	Description	Eng	Draft	Date	Client		Project	THREDBO ALPINE RESORT FRIDAY FLAT CAR PARK 2	Sheet Subject	SECTION SHEET 2	Scale: A1 1:100	Drawn WW	Authorised SB
P3	DA SUBMISSION	EC	JW	10.01.18																											
P2	DA SUBMISSION	EC	JW	20.12.18																											
P1	DA SUBMISSION	EC	JW	18.12.18																											
Rev	Description	Eng	Draft	Date																											
								Job No 181487	Drawing No C505	Revision P3																					
								Plot File Created: Jan 10, 2019 - 2:10pm																							

